

## Gas and Water vapour Permeability - PVDF Film

Film Thickness (um)	Gas	Unit	Value	Test Method
30	Oxygen	Cc/m <sup>2</sup> - day	118	ASTM D -3985
50			71	
60			62	
50	Carbon Dioxide		450	
50	Nitrogen		42	
50	Water vapour	g/m <sup>2</sup> - day	21	ASTM F-372-94
60			17	